

**QUOTE**  
**For a Dump Box, Wing/Front Plows and V-Box Sander**  
**For a 2019 Tandem Truck**  
**Specifications**

<p><b><u>14'6" Crvsteel Select Dump Body</u></b>          Body ID: 84"; Body OD: 96"          Side Height: 36"; Rear Height: 44"          7 GA 201 Stainless Steel Front, Side and Rear Material          Tailgate with Full Ribbed Dougle Wall Bracing          ¼" AR450 Floor          8" Western Tubular Understructure          Stainless Steel Rear Pillars, Cap, and Rubrail          Air Release Tailgate          Backup Alarm          Front and Rear Mudflaps          (2) Stainless Steel Shovel Holders          3 Oval Cutouts in Rear Pillars for Lights          Cougar Dump Body Vibrator          8" High Composite Boards          License Plate Bracket          Stainless Steel ½ Cabshield          Steps Inside of the Body          Driver's Side Front Stainless Steel Ladder          Stainless Steel Grab Handle          18"x18"x30" Stainless Steel Toolbox Mounted              to Frame of Truck          Not Painted (Bare Stainless Steel)          2 Pair of Tow Hooks, Front and Rear          Undercoated          Installed</p>	<p><b><u>Hoist Package</u></b>          Telescopic Hoist          Double Acting          Mailhot Hoist          Trunion Mounted          Dual Body Props          Hoist Stabilizer Kit</p> <p><b><u>Hitch Package:</u></b>          1" Pintle Plate</p> <p><b><u>Safety Lighting Package</u></b>          LED Amber Spinner Light          LED Clear Wing Light          (1) Whelen LED Strobe mounted on Cabshield          (2) Whelen Corners Strobes in Rear Pillars with              Stainless Steel Shields          LED Marker and Clearance Lights          (2) LED Strobes, (2) LED S/T/T, (2) LED Backup              Lights in Rear Pillars          Truck Lite Plow Lights with Heated Lenses Installed              On Stainless Steel Light Brackets          3M Reflective Tape          8.5" Heated Convex Mirror          Wired to Factory Switches</p>
<p><b><u>Truck Portion Plow Hitch</u></b>          Loop and Pin          Flat Fold Lift Arm          4" x 10" DA Lift Cylinder          Heavy Duty Front Bumper          Powdercoat Black</p>	<p><b><u>13' Reversible Plow</u></b>          Moldboard Length – 13'          10 Gauge Roll Formed Moldboard          1/2"x4" Tapered one piece Flame Cut Ribs          2"x3"x3/8" Top Angle          4"x4"x3/4" Bottom Angle          Horizontal Moldboard Angle Bracing          5/8"x8" Top Punched Cutting Edge          Dual Compression Trip Spring Assemblies for Full              Moldboard Trip          4"x4"x3/8" Cross-Tube Support          Moldboard &amp; Pushframe are to be 100%              Continuously Welded          Moldboard Powder Coated –Black          Push Frame Powder Coated – Black          Boxed Bottom Angle          Six Attachment Points          36" Fluorescent Markers          Weld on Loop and Pin Hitch          Rubber Snow Deflector          Custom Bolt on Top Angle for 13' Plow to Turn the Snow              Deflector Vertical          Two cast Moldboard Shoes          Screw Adjustable Parking Jack</p>

<p><b><u>9' Double Function Patrol Wing</u></b>  Tapered Moldboard (Right Side)  Front Mount Paraglide Wing Post per US Patent #8.596.376  31" High Inboard, 36.5" Outboard, 3/16" Thick Moldboard  4"x4"x3/4" Bottom Angle  1/2" Thick One-Piece Vertical &amp; Interlaced Designed  Horizontal Ribs  Mailbox Trim on Discharge End  Standard 100% Welded  Shot Blasted &amp; Powder Coated Black  Powder Coated Black Hardware  Wing Side Air Bag Kit  Check Valve for Heel and Toe  D-Cell Heel Lift Cylinder  36" Fluorescent Markers on Toe and Heel  Hydraulic Extendable Pusharm  Two Cast Moldboard Shoes  Installed</p>	<p><b><u>14' Stainless Steel V-Box Spreader</u></b>  201 Stainless Steel (Bare Stainless Steel, Not Painted)  14' Long x 56" Tall x 84" Wide  10 Gauge Hopper  7 Gauge Formed Lon-Sills Slotted for Drive and Idler  Shaft Removal  2 Drive &amp; Idler Shafts  Heavy Duty 4 Bolt Flange Bearings  45 Degree Sloped Sides  20" Drag Chain with 3/8"x1-1/2" Crossbars, 2-1/4" on  Center; Crossbar on Every Link Chain  Rear Slack Adjusters  Top Grate Kit with 5" Openings  Additional Pair of Lift Loops for Front of Hopper  4 Corner Lift System  50:1 Gear Box  White Hydraulic Motor  Mild Steel Top Grate Kit  Bearing Grease Extension Kit  8 Tooth Cast Iron Sprockets  Stainless Steel Leg Kit  Tip Up Spinner  Pair of Front Tie Downs for V Box with Stainless  Steel Brackets  Pin Top Rear of V Box into Upper Pivot Pin Holes  For Tailgate  Swing Open Tailgate for V Box  Minimizer Poly Fenders over Tandems</p>
<p><b><u>Hydraulics Package</u></b>  6.0 CID Front Mount Load Sense Pump  30 Gallon Capacity Stainless Hydraulic Reservoir  With Internal Filter  Filler/Breather Cap, Level/Temp Sight Glass, 3/4"  Magnetic Plug  60 P.S.I. Condition Indicator  Stainless Enclosure with Weather Tight Cover  Hydraulic Enclosure will be Mounted on Frame Rail  Dual Flow Spreader Control  1/4 Turn Ball Valve Pressure Line on Pump  Stainless Steel Tubes with Short Hoses for Spreader, Front  Hitch, Plow, Front Broom, Front Wing &amp; Front Pump  Functions  Installed  <u>Valve Sections</u>  D/A Plow Lift; D/A Plow Angle; D/A Hoist; D/A Wing Toe;  D/A Wing Heel; Hydraulic Pusharm; S/A Spreader on/off;  S/A Broom High Flow  Force Patrol Commander Ultra 5100 EX Joystick Package</p>	

**Total Quoted for a Dump Box, Wing/Front Plows,  
V-Box Sander as per Specs**

**\$ \_\_\_\_\_**

**Date of Delivery: \_\_\_\_\_**

**General Information/Instructions**

**For a Dump Box, Wing/Front Plows & V-Box Sander  
For a 2019 Tandem Dump Truck Chassis**

- 1) All quotes shall be placed in a sealed envelope and marked “Dump Box, Wing/Front Plows & V-Box Sander for a 2019 Tandem Dump Truck Chassis”.

Mail quotes to: Jeannette Atkinson, Clerk/Treasurer, Town of Wascott, PO Box 159, Wascott, WI 54890.

**Quotes are due by Noon, Friday, February 23, 2018. Opening of Quotes will take place at a Special Town Board Meeting on Friday, February 23 at 12:30 p.m.**

**Award of quotes will take place at the Regular Town Board Meeting to be held on Tuesday, March 6, 2018 at 7:00 p.m. at the Wascott Town Hall.**

- 1) All equipment furnished under this spec *shall* be new, unused, and from current production. The word “*shall*” indicates a mandatory requirement (no deviations). All other requirements are approximate. Deviations from approximate specifications considered “minor” by the Highway Foreman will be allowed. Deviations considered “major” will not be allowed. The determination of the Highway Foreman will be based upon whether or not the deviation is counter to the intent of the spec and *shall* be final.
- 2) The dealer *shall* be responsible for furnishing the units to the Town appointed body vendor. The dealer can use central Wisconsin as the location of the appointed body vendor. If the body vendor chooses to sub-contract painting, rust-proofing, or the installation of any accessories, the vendor *shall* be responsible for coordinating the work with the sub-contractor to insure both continuity and compliance to this spec. The Town reserves the right to reject quotes from dealers/vendors who are not factory authorized parts and service dealers.
- 3) The quote must comply with all material requirements of the invitation and specifications. The Town of Wascott reserves the right to reject any quote determined to be nonresponsive. Further, the Town of Wascott reserves the right to reject any or all quotes, or any portion of quote, as determined to be in the best interest of the Town.
- 4) Manufacturer’s full and detailed cuts and specs for the equipment quoted must be attached.
- 5) The date on or before which the equipment will be delivered, *must* be stated on the quote. This stated date of delivery *shall* be part of the quote and may be used in evaluating quotes.
- 6) The body vendor *shall* be responsible for delivering the equipment to the Town of Wascott
- 7) If the equipment is not delivered on or before the specified date, complete and ready for use, there will be a \$50.00 per calendar day charge deducted from the final payment for each day after this date for late delivery charge. The forfeiture shall not apply if the late delivery is due to items beyond the control of the vendor submitting the primary quotation – fire, strike, war, government prohibition, requisition by government of essential property or preferential government orders.
- 8) All quotations *shall* be firm for at least 45 days from proposal opening date.  
A written notice of award will be given to the successful bidder. The bidder(s) are required to execute the public contract and furnish required certificates of insurance within ten (10) calendar days from the date of the notice of award.
- 9) Payment shall be made within 30 days of receipt of a properly completed invoice or receipt and acceptance of the property or service.
- 10) If you have any questions, please contact Highway Foreman Jason Walters at 715/296-6875.

Company Name \_\_\_\_\_ Contact Person \_\_\_\_\_

Address \_\_\_\_\_

Phone Number \_\_\_\_\_ Email \_\_\_\_\_

Date \_\_\_\_\_